



ADDENDUM No. 4.

Corporate Office
 324 Evans St
 Greenville
 NC 27858
 Tel 252.758.3746
 Fax 252.830.3954

Raleigh Office
 4325 Lake Boone Trail
 Suite 311
 Raleigh
 NC 27607
 Tel 919.784.9330
 Fax 919.784.9331

www.eastgroup.com

Client / Facility: Craven Community College	TEG Project No.: 20170030
Project Name: Testing Center Renovations Barker Hall	
Prepared By: Procopio Serrano, AIA	Date Prepared: 5/19/2017

Attention: Please notify the author of any omissions or inaccuracies within ten working days after date prepared. Unless notified, the information contained in the meeting minutes will be considered correct as written.

Clarifications

- Clarification:** Change Floor finish for hallway 209 and hallway 213 from carpet to LVT. There will be no carpet this project area. See revised A8.1.
- Clarification:** Specification 09111 Non-Loadbearing Steel framing, page 2, item 2.2-E. Cold-Rolled Channel Bridging. As long as both sides of the wall has gypsum board, no additional cold rolled channel bridging is required in the wall, since these are non-loadbearing walls.
- Clarification:** New door 209 and new frame. Revise frame to be a F3 designation rather than a F1 previously noted. See revised A8.1.

Drawings:

- Revised drawing:** A8.1.

Specifications:

- NONE

REMINDER:

Sealed Bids (hard copy) are due **Tuesday May 23, 2017 at Brock Administration Building, Room 222, 800 College Court, New Bern NC** on the Campus of Craven Community College. Single prime bids will be accepted up until 2:00 PM EST. The bids will, immediately thereafter, be publicly opened and read aloud.

Attachments:

Revised Drawings: A8.1.

ENGINEERING
 -
 ARCHITECTURE
 -
 SURVEYING
 -
 TECHNOLOGY
 -

